ALUR MUNICIPALITY, HASSAN DISTRICT.

Notification dated 31st March 1925.

Notice is hereby given that sealed tenders will be received at the President's office, Municipal Council, Alur, up to 4 P.M. on 15th April 1925, for constructing a Municipal Office at Alur in the vacant site of the Sub-Taluk Office at Alur. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of October 1925.

2. The plans, detailed estimate and conditions may be seen at the Municipal Office on any day during office hours.

3. Tenders should be submitted on printed forms. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 150 (one hundred and fifty) in cash or Government promissory notes, as earnest money and be superscribed "Tender for constructing a Municipal Office building" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the President, Municipal Council, Alur, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender, subject to the approval of the Deputy Commissioner.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted, will be posted on the notice board in the Municipal Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. In matters of all disputes about rates, measurements, quantity of work, etc., and in all disputes of any kind, the decision of the President will be final and legally binding.

Abstract estimate of quantity for constructing a Municipal Office in the vacant site of the Sub-Taluk Office at Alur in Hassan District.

No.	Items of work	Per	Quantity
1	Earthwork, excavation in gravelly soil and fitting in basement	C.yds.	115
2	Concrete with stone jelly and lime mortar	C.ft.	895
3	Foundation with rough stone in lime mortar with through stones here and there.	„	1,920
4	Basement in size burnt stone in lime mortar with through stones here and there.	„	1,027
5	Arch work with burnt brick in chunam	„	145
6	Superstructure do do	„	3,953
7	Burnt stone slabs 6" thick dressed	S.ft.	651
8	Honne or nandi wood work wrought and put up including wood oiling, etc.	C.ft.	177·42
9	Roofing with 1st class Mangalore tiles on teak reepers, etc., complete	Sq.	16·38
10	Terrace 9" thick as per specification	„	3·22
11	Ridge tiles set in mortar	R.ft.	39
12	Plastering with chunam	Sq.	62·38
13	White and colour washing two coats	„	62·38
14	Teakwood panelled doors with all iron fittings, etc., complete	S.ft.	224
15	Teakwood windows with iron bars inside glased, outside panelled shutters, etc., complete.	„	144
16	Teakwood ventilators with glased shutters, etc., iron bars	„	54
17	Teakwood circular ventilators	„	10
18	Flooring with 1st class Mangalore square tiles over 3" concrete bed and cement pointing, etc., complete.	Sq.	10·03
19	Ornamental cornice work 9" deep	R.ft.	344
20	Do parapet wall with plastering cornice at top and base at bottom, etc.	„	71
21	Dwarf walls at gable ends	„	84
22	Pointing with chunam basement	Sqr.	3·12
23	Masonry pillars with base and capital including plastering, etc., complete	No.	6
24	Cement charges for three arches	..	..

B. VENKATARAMA RAO,
President.